


FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
1		450	5.2M	PIPE ANSI B36 10 PE SMLS PIPE STD
2		600 x 450	1	FITTINGS REDU ECC ANSI B16.9 BW STD
3		450 x 300	1	REDU ECC ANSI B16.9 BW STD
4		450 x 20	2	BONNEY THREDOLET NPT #3000
5		450	4	ELBOW LR ANSI B16.9 BW
6		20	4	NIPPLE TBE NPT 3" LONG XS
7		20	2	CAP SCR D ANSI B16.11 #3000
8		450	6	FLANGES FLANGE WN ANSI B16.5 #150.RF
9		300	1	FLANGE WN ANSI B16.5 #150.RF

ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
10		450	5	GASKETS GASKET ANSI B16.21 #150.RF
11		300	1	GASKET ANSI B16.21 #150.RF
12		29	80	BOLTS 146 STUD BOLT CW HVY HEX NUTS
13		22	12	114 STUD BOLT CW HVY HEX NUTS
14		450	2	VALVES / IN-LINE ITEMS VALVE GATE ANSI B16.10 #150.RF
15		20	2	VALVE GATE NPT #800
16	12A-450-12-300/300-S	450	1	SUPPORTS PIPE SUPPORT TRUNNION SLIDE (ELBOW)
17	12B-450-12-300/300-S	450	1	PIPE SUPPORT TRUNNION SLIDE (PIPE)



TEMPORARY ISO

TEMPORARY ISO DRAWING

ALL RIGHTS RESERVED THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT,DATA,OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER,EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.		
FOR		
TITLE PIPING ISOMETRIC DRAWING FOR		
LINE_ID:	18"-PHE-B1-N-N-IN2	1 OF 1
AREA	18"-PHE-B1-N-N-IN2	
SCALE	NONE	JOB NO. AHH20E
PROJECT	DRAWING NO.	REVISION
CAP	CAP-XX-XX-DW-XXXX	
	18"-PHE-B1-N-N-IN2	

REV	DATE	DGND	CHKD	APRD	APRD	DESCRIPTION

WORK NO.

TEMPORARY ISO

EXTRACT DATE : 02 OCT 2019 08:00 ( )