



FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
				<u>PIPE</u>
1		400	6.2M	ANSI B36 10 PE SMLS PIPE STD
2		40	0.2M	ANSI B36 10 PE SMLS PIPE XS
				<u>FITTINGS</u>
3		600 x 400	1	REDU ECC ANSI B16.9 BW STD
4		400 x 300	1	REDU ECC ANSI B16.9 BW STD
5		400 x 40	1	BONNEY THREDOLET NPT #3000
6		400 x 20	2	BONNEY THREDOLET NPT #3000
7		400	2	ELBOW LR ANSI B16.9 BW
8		20	4	NIPPLE TBE NPT 3" LONG XS
9		20	2	CAP SCR D ANSI B16.11 #3000
				<u>FLANGES</u>
10		400	4	FLANGE WN ANSI B16.5 #150.RF
11		300	1	FLANGE WN ANSI B16.5 #150.RF
12		40	1	FLANGE SCR BOSS ANSI B16.5 #150.RF

ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
FLANGES				
13		40	1	FLANGE BLIND ANSI B16.5 #150.RF
GASKETS				
14		400	5	GASKET ANSI B16.21 #150.RF
15		300	1	GASKET ANSI B16.21 #150.RF
16		40	1	GASKET ANSI B16.21 #150.RF
BOLTS				
17		25	16	140 STUD BOLT CW HVY HEX NUTS
18		25	48	133 STUD BOLT CW HVY HEX NUTS
19		22	12	114 STUD BOLT CW HVY HEX NUTS
20		13	4	70 STUD BOLT CW HVY HEX NUTS
VALVES / IN-LINE ITEMS				
21		400	1	VALVE GATE ANSI B16.10 #150.RF
22		20	2	VALVE GATE NPT #800
SUPPORTS				
23	12A-400-15-250/250-S	400	1	PIPE SUPPORT TRUNNION SLIDE (ELBOW)
24	12B-400-15-250/250-S	400	1	PIPE SUPPORT TRUNNION SLIDE (PIPE)



TEMPORARY ISO DRAWING

REV	DATE	DGND	CHKD	APRD	APRD	DESCRIPTION

ALL RIGHTS RESERVED THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT,DATA,OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER,EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.		
FOR		
		
TITLE PIPING ISOMETRIC DRAWING FOR		
LINE_ID: 16"PHE-A2-N-Y-S2 1 OF 1		
AREA : 16"PHE-A2-N-Y-S2		
SCALE	NONE	JOB NO. AHH20E
PROJECT	DRAWING NO.	REVISION
CAP	CAP-XX-XX-DW-XXXX	
	16"PHE-A2-N-Y-S2	

WORK NO.

EXTRACT DATE : 02 OCT 2019 08:00 ()