


FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
1		600	1.4M	PIPE
		250	6.9M	ANSI B36 10 PE SMLS PIPE STD
2				ANSI B36 10 PE SMLS PIPE STD
FITTINGS				
3		600 x 250	1	TEE ANSI B16.9 BW STD
4		600	1	ELBOW LR ANSI B16.9 BW
5		250 x 25	1	BONNEY THREDOLET NPT #3000
6		250	4	ELBOW LR ANSI B16.9 BW
7		25	2	NIPPLE TBE NPT 3" LONG XS
8		25	1	CAP SCR D ANSI B16.11 #3000
FLANGES				
9		250	1	FLANGE WN ANSI B16.5 #150.RF
ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
GASKETS				
10		250	3	GASKET ANSI B16.21 #150.RF
BOLTS				
11		22	12	121 STUD BOLT CW HVY HEX NUTS
12		22	12	114 STUD BOLT CW HVY HEX NUTS
VALVES / IN-LINE ITEMS				
13		250	1	VALVE GATE ANSI B16.10 #150.RF
14		25	1	VALVE GATE NPT #800



TEMPORARY ISO DRAWING

ALL RIGHTS RESERVED THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT,DATA,OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER,EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.		
FOR		
TITLE ----- PIPING ISOMETRIC DRAWING FOR -----		
LINE_ID: 10"-CV-B1-USDD-IN 1 OF 4		
AREA : 10"-CV-B1-USDD-IN		
SCALE	NONE	JOB NO. AHH20E
PROJECT	DRAWING NO.	REVISION
CAP	CAP-XX-XX-DW-XXXX	
	10"-CV-B1-USDD-IN	

REV	DATE	DGND	CHKD	APRD	APRD	DESCRIPTION

WORK NO.

EXTRACT DATE : 26 AUG 2019 17:05 ()