


FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
1		100	9.7M	PIPE
				ANSI B36 10 PE SMLS PIPE STD
2		20	0.2M	ANSI B36 10 PE SMLS PIPE XS
FITTINGS				
3		250 x 100	1	REDU ECC ANSI B16.9 BW STD
4		100 x 100	1	TEE ANSI B16.9 BW STD
5		100 x 20	2	BONNEY THREDOLET NPT #3000
6		100	3	ELBOW LR ANSI B16.9 BW
FLANGES				
7		100	6	FLANGE WN ANSI B16.5 #150.RF
ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
8		100	7	GASKETS
				GASKET ANSI B16.21 #150.RF
9		16	8	BOLTS
				163 STUD BOLT CW HVY HEX NUTS
				95 STUD BOLT CW HVY HEX NUTS
10		16	8	89 STUD BOLT CW HVY HEX NUTS
VALVES / IN-LINE ITEMS				
12		100	1	VALVE WFR CHK MISSION K #150.RF
13		100	1	VALVE GATE ANSI B16.10 #150.RF
14		20	2	VALVE GATE NPT #800
INSTRUMENTS				
15	FCV-2201	100	1	GLOBE VALVE
SUPPORTS				
16	11B-100-05-80	100	1	PIPE SUPPORT TRUNNION FIX (PIPE)



TEMPORARY ISO DRAWING

ALL RIGHTS RESERVED THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT, DATA OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.		
FOR		
TITLE PIPING ISOMETRIC DRAWING FOR		
LINE_ID: 10"-ET-B2-H-H-L-MIN-A 1 OF 1		
AREA : 10"-ET-B2-H-H-L-MIN-A		
SCALE	NONE	JOB NO. AHH20E
PROJECT	DRAWING NO.	REVISION
CAP	CAP-XX-XX-DW-XXXX	
	10"-ET-B2-H-H-L-MIN-A	

REV	DATE	DGND	CHKD	APRD	APRD	DESCRIPTION