


FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
1		250	1.7M	<u>PIPE</u>
				ANSI B36 10 PE SMLS PIPE STD
2		20	0.1M	ANSI B36 10 PE SMLS PIPE XS
3		250 x 20	1	<u>FITTINGS</u>
				BONNEY THREDOLET NPT #3000
4		250	3	ELBOW LR ANSI B16.9 BW
5		250	3	<u>FLANGES</u>
				FLANGE WN ANSI B16.5 #150.RF
ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
6		250	4	<u>GASKETS</u>
				GASKET ANSI B16.21 #150.RF
7		22	12	<u>BOLTS</u>
				121 STUD BOLT CW HVY HEX NUTS
8		22	24	114 STUD BOLT CW HVY HEX NUTS
9		250	1	<u>VALVES / IN-LINE ITEMS</u>
				VALVE GATE ANSI B16.10 #150.RF
10		20	1	VALVE GATE NPT #800
11	12A-250-06-150/150	250	1	<u>SUPPORTS</u>
				PIPE SUPPORT TRUNNION SLIDE (ELBOW)
12	12C-250-06-150/150	250	1	PIPE SUPPORT TRUNNION SLIDE (TEE)



TEMPORARY ISO DRAWING

ALL RIGHTS RESERVED THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT,DATA,OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER,EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.		
FOR		
TITLE ----- PIPING ISOMETRIC DRAWING FOR -----		
LINE_ID: 8"-FS-A2-2-G-DIS(A) 1 OF 1		
AREA : 8"-FS-A2-2-G-DIS(A)		
SCALE	NONE	JOB NO. AHH20E
PROJECT	DRAWING NO.	REVISION
CAP	CAP-XX-XX-DW-XXXX	
	8"-FS-A2-2-G-DIS(A)	

REV	DATE	DGND	CHKD	APRD	APRD	DESCRIPTION