


FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
1 2 3		400	0.2M	PIPE ANSI B36 10 PE SMLS PIPE STD
		250	6.0M	ANSI B36 10 PE SMLS PIPE STD
		20	0.1M	ANSI B36 10 PE SMLS PIPE XS
4 5 6 7 8 9		FITTINGS		
		400 x 250	1	REDU ECC ANSI B16.9 BW STD
		400	1	ELBOW LR ANSI B16.9 BW
		250 x 250	1	TEE ANSI B16.9 BW STD
		250 x 200	2	REDU ECC ANSI B16.9 BW STD
		250 x 20	1	BONNEY THREDOLET NPT #3000
10 11 12		250	2	ELBOW LR ANSI B16.9 BW
		FLANGES		
		400	1	FLANGE WN ANSI B16.5 #150.RF
		250	2	FLANGE WN ANSI B16.5 #150.RF
		200	2	FLANGE WN ANSI B16.5 #150.RF

ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
13 14		400	1	GASKETS GASKET ANSI B16.21 #150.RF
		250	2	GASKET ANSI B16.21 #150.RF
		BOLTS		
15 16		25	16	133 STUD BOLT CW HVY HEX NUTS
		22	24	114 STUD BOLT CW HVY HEX NUTS
17 18		VALVES / IN-LINE ITEMS		
		250	1	VALVE GATE ANSI B16.10 #150.RF
		20	1	VALVE GATE NPT #800
19	27-250-08-05-C12	SUPPORTS		
		250	1	PIPE SUPPORT GATE TYPE



TEMPORARY ISO DRAWING

ALL RIGHTS RESERVED THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT, DATA OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.		
FOR		
TITLE PIPING ISOMETRIC DRAWING FOR		
LINE_ID: A"-HE-C-3-T2-OUT(D) 1 OF 3		
AREA : A"-HE-C-3-T2-OUT(D)		
SCALE NONE	JOB NO. AHH20E	
PROJECT CAP	DRAWING NO. CAP-XX-XX-DW-XXXX A"-HE-C-3-T2-OUT(D)	REVISION