



FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
1 2 3		350	5.5M	PIPE ANSI B36 10 PE SMLS PIPE STD
		250	0.2M	ANSI B36 10 PE SMLS PIPE STD
		20	0.3M	ANSI B36 10 PE SMLS PIPE XS
4 5 6 7		FITTINGS		
		350 x 350	1	TEE ANSI B16.9 BW STD
		350 x 250	1	REDU CONC ANSI B16.9 BW STD
		350 x 20	3	BONNEY THREDOLET NPT #3000
		350	5	ELBOW LR ANSI B16.9 BW
8 9		FLANGES		
		350	4	FLANGE WN ANSI B16.5 #150.RF
		250	1	FLANGE WN ANSI B16.5 #150.RF

ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
10 11		GASKETS		
		350	5	GASKET ANSI B16.21 #150.RF
		250	1	GASKET ANSI B16.21 #150.RF
		BOLTS		
		25	12	306 STUD BOLT CW HVY HEX NUTS
12		25	12	133 STUD BOLT CW HVY HEX NUTS
13		25	12	127 STUD BOLT CW HVY HEX NUTS
14		25	12	114 STUD BOLT CW HVY HEX NUTS
15		22	12	114 STUD BOLT CW HVY HEX NUTS
16 17 18		VALVES / IN-LINE ITEMS		
		350	1	VALVE WFR CHK MISSION K #150.RF
		350	1	VALVE GATE ANSI B16.10 #150.RF
		20	3	VALVE GATE NPT #800
19 20		INSTRUMENTS		
		20	1	PRESSURE GAUGE
21 22		SUPPORTS		
		20	1	PIPE SUPPORT TRUNNION WITH ADJUSTABLE BOLT (ELBOW)
23 24		350	1	PIPE SUPPORT TRUNNION FIX (ELBOW)
		350	1	PIPE SUPPORT TRUNNION FIX (ELBOW)



TEMPORARY ISO DRAWING

ALL RIGHTS RESERVED THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT, DATA OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.		
FOR		
		
TITLE PIPING ISOMETRIC DRAWING FOR		
LINE_ID: 14"-TT-A1-S-G-N-DIS-A 1 OF 1		
AREA : 14"-TT-A1-S-G-N-DIS-A		
SCALE	NONE	JOB NO. AHH20E
PROJECT	DRAWING NO.	REVISION
CAP	CAP-XX-XX-DW-XXXX	
	14"-TT-A1-S-G-N-DIS-A	

REV	DATE	DGND	CHKD	APRD	APRD	DESCRIPTION

WORK NO.