



FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
1		600	0.2M	PIPE
		250	6.2M	ANSI B36 10 PE SMLS PIPE STD
2				ANSI B36 10 PE SMLS PIPE STD
FITTINGS				
3		600 x 250	1	TEE ANSI B16.9 BW STD
4		250 x 25	1	BONNEY THREDOLET NPT #3000
5		250	4	ELBOW LR ANSI B16.9 BW
6		25	2	NIPPLE TBE NPT 3" LONG XS
7		25	1	CAP SCRD ANSI B16.11 #3000
FLANGES				
8		250	1	FLANGE WN ANSI B16.5 #150.RF
ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
GASKETS				
9		250	2	GASKET ANSI B16.21 #150.RF
BOLTS				
10		22	12	121 STUD BOLT CW HVY HEX NUTS
VALVES / IN-LINE ITEMS				
11		25	1	VALVE GATE NPT #800



ALL RIGHTS RESERVED  
THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT,DATA,OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER,EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.

FOR

**CHIYODA CORPORATION**

TITLE

PIPING ISOMETRIC DRAWING FOR

LINE\_ID:

10"-CN-B2-USDD-IN

2 OF 4

AREA

: 10"-CN-B2-USDD-IN

SCALE

NONE

JOB NO.

AHH20E

PROJECT


DRAWING NO.

REVISION

CAP

CAP-XX-XX-DW-XXXX

10"-CN-B2-USDD-IN



TEMPORARY ISO DRAWING

REV	DATE	DGND	CHKD	APRD	APRD	DESCRIPTION

WORK NO.