


FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
1		150	4.2M	PIPE
				ANSI B36 10 PE SMLS PIPE STD
2		20	0.2M	ANSI B36 10 PE SMLS PIPE XS
FITTINGS				
3		150 x 150	1	TEE ANSI B16.9 BW STD
4		150 x 20	2	BONNEY THREDOLET NPT #3000
5		150	2	ELBOW LR ANSI B16.9 BW
FLANGES				
6		150	3	FLANGE WN ANSI B16.5 #150.RF

ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
GASKETS				
7		150	4	GASKET ANSI B16.21 #150.RF
BOLTS				
8		19	24	95 STUD BOLT CW HVY HEX NUTS
VALVES / IN-LINE ITEMS				
9		150	2	VALVE GATE ANSI B16.10 #150.RF
10		20	2	VALVE GATE NPT #800
SUPPORTS				
11	14A-150-05-100/100	150	1	PIPE SUPPORT TRUNNION WITH ADJUSTABLE BOLT (ELBOW)



ALL RIGHTS RESERVED
THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT,DATA,OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER,EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.

FOR

CHIYODA CORPORATION

TITLE
PIPING ISOMETRIC DRAWING FOR

LINE_ID: 6"-SS-C1-H-H-SUC-A 1 OF 2

AREA : 6"-SS-C1-H-H-SUC-A

SCALE	NONE	JOB NO.	AHH20E
PROJECT	DRAWING NO.	REVISION	
CAP	CAP-XX-XX-DW-XXXX	6"-SS-C1-H-H-SUC-A	