FABRICATION MATERIALS

NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
				PIPE
1		80	4.1M	ANSI B36 10 PE SMLS PIPE STD
2		50	0.3M	ANSI B36 10 PE SMLS PIPE XS
3		20	0.3M	ANSI B36 10 PE SMLS PIPE XS
				FITTINGS
4		80 x 80	1	TEE ANSI B16.9 BW STD
5		80 x 50	1	REDU CONC ANSI B16.9 BW STD
6		80 x 20	3	BONNEY THREDOLET NPT #3000
7		80	3	ELBOW LR ANSI B16.9 BW
				FLANGES
8		80	4	FLANGE WN ANSI B16.5 #150.RF
9		50	1	FLANGE WN ANSI B16.5 #150.RF

ERECTION MATERIALS

NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
				GASKETS
10		80	5	GASKET ANSI B16.21 #150.RF
11		50	1	GASKET ANSI B16.21 #150.RF
				BOLTS
12		13	4	163 STUD BOLT CW HVY HEX NUTS
13		13	4	95 STUD BOLT CW HVY HEX NUTS
14		13	4	89 STUD BOLT CW HVY HEX NUTS
15		13	4	76 STUD BOLT CW HVY HEX NUTS
				VALVES / IN-LINE ITEMS
16		80	1	VALVE WFR CHK MISSION K #150.RF
17		80	1	VALVE GATE ANSI B16.10 #150.RF
18		20	1	VALVE GLOBE VOGT NPT #800
19		20	2	VALVE GATE NPT #800
				INSTRUMENTS
20	PG_102_11_10_1070_1E	20	1	PRESSURE GAUGE
				SUPPORTS
21	12A-80-06-50/80	80	1	PIPE SUPPORT TRUNNION SLIDE (ELBOW)



TEMPORARY ISO

TEMPORARY ISO DRAWING

REV	DATE	DGND	CHKD	APRD	APRD	DESCRIPTION

ALL RIGHTS RESERVED
THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT,DATA,OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER,EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.

FOR

CHIYODA CORPORATION

TITLE

PIPING ISOMETRIC DRAWING FOR

LINE_ID: 6"-SS-A1-V-V-DIS-A 1 OF 1

AREA : 6"-SS-A1-V-V-DIS-A

SCALE NONE | JOB NO. AHH20E

PROJECT: CAP

DRAWING NO.: CAP-XX-XX-DW-XXXX

6"-SS-A1-V-V-DIS-A

REVISION

WORK NO.

EXTRACT DATE : 24 JUL 2019 13:35 ()

TEMPORARY ISO
6"-SS-A1-V-V-DIS-A