



FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
1		600	0.8M	PIPE
		250	5.2M	ANSI B36 10 PE SMLS PIPE STD
2				ANSI B36 10 PE SMLS PIPE STD
FITTINGS				
3		600 x 250	2	TEE ANSI B16.9 BW STD
4		600	1	CAP LONG ANSI B16.9 BW STD
5		250	4	ELBOW LR ANSI B16.9 BW
FLANGES				
6		250	2	FLANGE WN ANSI B16.5 #150.RF
ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
GASKETS				
7		250	6	GASKET ANSI B16.21 #150.RF
BOLTS				
8		22	24	121 STUD BOLT CW HVY HEX NUTS
9		22	24	114 STUD BOLT CW HVY HEX NUTS
VALVES / IN-LINE ITEMS				
10		250	2	VALVE GATE ANSI B16.10 #150.RF



TEMPORARY ISO DRAWING

ALL RIGHTS RESERVED THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT,DATA,OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER,EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.		
FOR		
		
TITLE PIPING ISOMETRIC DRAWING FOR		
LINE_ID:	10"-CV-B1-UOUD-IN	2 OF 2
AREA	10"-CV-B1-UOUD-IN	
SCALE	NONE	JOB NO. AHH20E
PROJECT	DRAWING NO.	REVISION
CAP	CAP-XX-XX-DW-XXXX	
	10"-CV-B1-UOUD-IN	