




FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
1		250	2.1M	<u>PIPE</u> ANSI B36 10 PE SMLS PIPE STD
2		250 x 100	1	<u>FITTINGS</u> REDU CONC ANSI B16.9 BW STD
3		250 x 25	1	BONNEY THREDOLET NPT #3000
4		250 x 20	1	BONNEY THREDOLET NPT #3000
5		250	1	ELBOW LR ANSI B16.9 BW
6		20	2	NIPPLE TBE NPT 3" LONG XS
7		20	2	NIPPLE TBE NPT 6" LONG XS
				<u>FLANGES</u>
8		250	4	FLANGE WN ANSI B16.5 #150.RF
9		100	1	FLANGE WN ANSI B16.5 #150.RF
10		20	2	FLANGE SO ANSI B16.5 #150.RF
ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
11		20	2	<u>FLANGES</u> FLANGE BLIND ANSI B16.5 #150.RF
				<u>GASKETS</u>
12		250	4	GASKET ANSI B16.21 #150.RF
13		100	1	GASKET ANSI B16.21 #150.RF
14		20	2	GASKET ANSI B16.21 #150.RF
				<u>BOLTS</u>
15		22	48	114 STUD BOLT CW HVY HEX NUTS
16		13	8	57 STUD BOLT CW HVY HEX NUTS
				<u>VALVES / IN-LINE ITEMS</u>
17		250	2	VALVE GATE ANSI B16.10 #150.RF
18		20	2	VALVE GATE NPT #800
				<u>INSTRUMENTS</u>
19	EV-3302	100	1	ANGLE VALVE
				<u>SUPPORTS</u>
20	42D-250-07-200	250	2	PIPE SUPPORT TRUNNION HORIZONTAL (PIPE)
21	28-250-04-07-A10-S	250	2	PIPE SUPPORT GUTTER TYPE FOR HORIZONTAL



ALL RIGHTS RESERVED
THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT,DATA,OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER,EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.

FOR		
		
TITLE		
PIPING ISOMETRIC DRAWING FOR		
LINE_ID: 10"-PRV-C2-H-V-IN 1 OF 1		
AREA : 10"-PRV-C2-H-V-IN		
SCALE	NONE	JOB NO. AHH20E
PROJECT	DRAWING NO.	REVISION
CAP	CAP-XX-XX-DW-XXXX	
	10"-PRV-C2-H-V-IN	

WORK NO.

EXTRACT DATE : 10 SEP 2019 17:03 ()