



FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
				<u>PIPE</u>
1	SETON TEE	350	2.7M	ANSI B36 10 PE SMLS PIPE STD
2		300	2.4M	ANSI B36 10 PE SMLS PIPE STD
3		50	0.1M	ANSI B36 10 PE SMLS PIPE XS
4		20	0.3M	ANSI B36 10 PE SMLS PIPE XS
				<u>FITTINGS</u>
5		350 x 350	1	TEE ANSI B16.9 BW STD
6		350 x 300	1	REDU CONC ANSI B16.9 BW STD
7		350 x 20	1	BONNEY THREDOLET NPT #3000
8		350	2	ELBOW LR ANSI B16.9 BW
				<u>FLANGES</u>
9		350	3	FLANGE WN ANSI B16.5 #150.RF
10		300	1	FLANGE WN ANSI B16.5 #150.RF
11		50	1	FLANGE WN ANSI B16.5 #150.RF

ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
FLANGES				
12		350	1	FLANGE BLIND ANSI B16.5 #150.RF
13		50	1	FLANGE BLIND ANSI B16.5 #150.RF
GASKETS				
14		350	2	GASKET ANSI B16.21 #150.RF
15		300	1	GASKET ANSI B16.21 #150.RF
16		50	2	GASKET ANSI B16.21 #150.RF
BOLTS				
17		25	12	127 STUD BOLT CW HVY HEX NUTS
18		22	12	114 STUD BOLT CW HVY HEX NUTS
19		13	4	76 STUD BOLT CW HVY HEX NUTS
VALVES / IN-LINE ITEMS				
20		50	1	VALVE GATE ANSI B16.10 #150.RF
21		20	1	VALVE GLOBE VOGT NPT #800
INSTRUMENTS				
22	PG_102_11_10_1070_1E	20	1	PRESSURE GAUGE





UNACCEPTABLE SPLIT

TEMPORARY ISO



TEMPORARY ISO DRAWING

ALL RIGHTS RESERVED THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT,DATA,OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER,EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.		
FOR		
		
TITLE ----- PIPING ISOMETRIC DRAWING FOR -----		
LINE_ID:	14"-TT-B1-S-S-N-SUC-B	2 OF 2
AREA	: 14"-TT-B1-S-S-N-SUC-B	
SCALE	NONE	JOB NO. AHH20E
PROJECT	DRAWING NO.	REVISION
CAP	CAP-XX-XX-DW-XXXX	
	14"-TT-B1-S-S-N-SUC-B	

REV	DATE	DGND	CHKD	APRD	APRD	DESCRIPTION