


FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
1 2 3		350	6.0M	PIPE ANSI B36 10 PE SMLS PIPE STD
		250	2.4M	ANSI B36 10 PE SMLS PIPE STD
		20	0.3M	ANSI B36 10 PE SMLS PIPE XS
4 5 6		350 x 250	1	FITTINGS REDU CONC ANSI B16.9 BW STD
		350 x 20	3	BONNEY THREDOLET NPT #3000
		350	4	ELBOW LR ANSI B16.9 BW
7 8		350	6	FLANGES FLANGE WN ANSI B16.5 #150.RF
		250	1	FLANGE WN ANSI B16.5 #150.RF
ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
9 10		350	6	GASKETS GASKET ANSI B16.21 #150.RF
		250	1	GASKET ANSI B16.21 #150.RF
11 12 13 14		25	12	BOLTS 306 STUD BOLT CW HVY HEX NUTS
		25	12	133 STUD BOLT CW HVY HEX NUTS
		25	24	127 STUD BOLT CW HVY HEX NUTS
		22	12	114 STUD BOLT CW HVY HEX NUTS
15 16 17 18		350	1	VALVES / IN-LINE ITEMS VALVE WFR CHK MISSION K #150.RF
		350	1	VALVE GATE ANSI B16.10 #150.RF
		20	1	VALVE GLOBE VOGT NPT #800
		20	2	VALVE GATE NPT #800
19	PG_102_11_10_1070_1E	20	1	INSTRUMENTS PRESSURE GAUGE
20	11A-350-06-250	350	1	SUPPORTS PIPE SUPPORT TRUNNION FIX (ELBOW)



TEMPORARY ISO DRAWING

REV	DATE	DGND	CHKD	APRD	APRD	DESCRIPTION

ALL RIGHTS RESERVED  
THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT, DATA OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.

FOR

CHIYODA CORPORATION

TITLE  
PIPING ISOMETRIC DRAWING FOR  
LINE\_ID: 14"-TT-A1-S-S-N-DIS-B 1 OF 1  
AREA : 14"-TT-A1-S-S-N-DIS-B

SCALE NONE JOB NO. AHH20E

PROJECT CAP DRAWING NO. CAP-XX-XX-DW-XXXX  
14"-TT-A1-S-S-N-DIS-B

REVISION

WORK NO.