


FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
PIPE				
1		250	5.1M	ANSI B36 10 PE SMLS PIPE STD
2		200	0.2M	ANSI B36 10 PE SMLS PIPE STD
3		20	0.2M	ANSI B36 10 PE SMLS PIPE XS
FITTINGS				
4		250 x 200	1	REDU CONC ANSI B16.9 BW STD
5		250 x 20	2	BONNEY THREDOLET NPT #3000
6		250	5	ELBOW LR ANSI B16.9 BW
FLANGES				
7		250	4	FLANGE WN ANSI B16.5 #150.RF
8		200	1	FLANGE WN ANSI B16.5 #150.RF
ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
GASKETS				
9		250	5	GASKET ANSI B16.21 #150.RF
10		200	1	GASKET ANSI B16.21 #150.RF
BOLTS				
11		22	12	262 STUD BOLT CW HVY HEX NUTS
12		22	12	121 STUD BOLT CW HVY HEX NUTS
13		22	12	114 STUD BOLT CW HVY HEX NUTS
14		19	8	102 STUD BOLT CW HVY HEX NUTS
VALVES / IN-LINE ITEMS				
15		250	1	VALVE WFR CHK MISSION K #150.RF
16		250	1	VALVE GATE ANSI B16.10 #150.RF
17		20	1	VALVE GLOBE VOGT NPT #800
18		20	1	VALVE GATE NPT #800
INSTRUMENTS				
19	PG_102_11_10_1070_1E	20	1	PRESSURE GAUGE
SUPPORTS				
20	14A-250-05-150/150	250	1	PIPE SUPPORT TRUNNION WITH ADJUSTABLE BOLT (ELBOW)
21	12A-200-05-150/150	250	1	PIPE SUPPORT TRUNNION SLIDE (ELBOW)





CONT. ON
10"-ET-A1-V-V-L-DIS-A
E 118198
N 30823
EL +2837



TEMPORARY ISO DRAWING

TEMPORARY ISO

ALL RIGHTS RESERVED THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT,DATA,OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER,EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.		
FOR		
		
TITLE PIPING ISOMETRIC DRAWING FOR		
LINE_ID: 10"-ET-A1-V-V-L-DIS-B 1 OF 1		
AREA : 10"-ET-A1-V-V-L-DIS-B		
SCALE	NONE	JOB NO. AHH20E
PROJECT	DRAWING NO.	REVISION
CAP	CAP-XX-XX-DW-XXXX	
	10"-ET-A1-V-V-L-DIS-B	

REV	DATE	DGND	CHKD	APRD	APRD	DESCRIPTION

WORK NO.

TEMPORARY ISO