


FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
1		400	4.7M	PIPE
				ANSI B36 10 PE SMLS PIPE STD
				FITTINGS
				REDU ECC ANSI B16.9 BW STD
				REDU ECC ANSI B16.9 BW STD
				BONNEY THREDOLET NPT #3000
				ELBOW LR ANSI B16.9 BW
2		20	2	NIPPLE TBE NPT 3" LONG XS
				CAP SCR D ANSI B16.11 #3000
3		400	2	FLANGES
				FLANGE WN ANSI B16.5 #150.RF
4		300	1	FLANGE WN ANSI B16.5 #150.RF

ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
10		400	2	GASKETS
				GASKET ANSI B16.21 #150.RF
				GASKET ANSI B16.21 #150.RF
11		300	1	BOLTS
				133 STUD BOLT CW HVY HEX NUTS
12		25	32	114 STUD BOLT CW HVY HEX NUTS
				VALVES / IN-LINE ITEMS
14		400	1	VALVE GATE ANSI B16.10 #150.RF
				VALVE GATE NPT #800
15		20	1	SUPPORTS
				PIPE SUPPORT TRUNNION SLIDE (ELBOW)
16	12A-400-15-250/250-S	400	1	PIPE SUPPORT TRUNNION SLIDE (PIPE)
17	12B-400-15-250/250-S	400	1	




TEMPORARY ISO DRAWING

REV	DATE	DGND	CHKD	APRD	APRD	DESCRIPTION

ALL RIGHTS RESERVED  
THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT,DATA,OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER,EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.

FOR

CHIYODA CORPORATION

TITLE  
PIPING ISOMETRIC DRAWING FOR  
LINE\_ID: 16"-PHE-A2-Y-N-S2 1 OF 1  
AREA : 16"-PHE-A2-Y-N-S2

SCALE NONE JOB NO. AHH20E  
PROJECT DRAWING NO. CAP-XX-XX-DW-XXXX  
CAP 16"-PHE-A2-Y-N-S2

REVISION

WORK NO.