




FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
				<u>PIPE</u>
1		450	4.0M	ANSI B36 10 PE SMLS PIPE STD
2		40	0.2M	ANSI B36 10 PE SMLS PIPE XS
				<u>FITTINGS</u>
3		600 x 600	1	TEE ANSI B16.9 BW STD
4		600 x 450	1	REDU ECC ANSI B16.9 BW STD
5		450 x 300	1	REDU ECC ANSI B16.9 BW STD
6		450 x 40	1	BONNEY THREDOLET NPT #3000
7		450	4	ELBOW LR ANSI B16.9 BW
				<u>FLANGES</u>
8		450	4	FLANGE WN ANSI B16.5 #150.RF
9		300	1	FLANGE WN ANSI B16.5 #150.RF
10		40	1	FLANGE SCR BOSS ANSI B16.5 #150.RF

ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
FLANGES				
11		40	1	FLANGE BLIND ANSI B16.5 #150.RF
GASKETS				
12		450	3	GASKET ANSI B16.21 #150.RF
13		300	1	GASKET ANSI B16.21 #150.RF
14		40	1	GASKET ANSI B16.21 #150.RF
BOLTS				
15		29	48	146 STUD BOLT CW HVY HEX NUTS
16		22	12	114 STUD BOLT CW HVY HEX NUTS
17		13	4	70 STUD BOLT CW HVY HEX NUTS
VALVES / IN-LINE ITEMS				
18		450	1	VALVE GATE ANSI B16.10 #150.RF
SUPPORTS				
19	12A-450-14-300/300-S	450	1	PIPE SUPPORT TRUNNION SLIDE (ELBOW)



TEMPORARY ISO DRAWING

ALL RIGHTS RESERVED THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT, DATA OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.		
FOR		
		
TITLE PIPING ISOMETRIC DRAWING FOR		
LINE_ID:	18"-PHE-A1-N-N-OUT2	1 OF 1
AREA :	18"-PHE-A1-N-N-OUT2	
SCALE	NONE	JOB NO. AHH20E
PROJECT	DRAWING NO.	REVISION
CAP	CAP-XX-XX-DW-XXXX	
	18"-PHE-A1-N-N-OUT2	
WORK NO.		

TEMPORARY ISO