




FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
1		150	1.3M	PIPE
		100	0.3M	ANSI B36 10 PE SMLS PIPE STD
2				ANSI B36 10 PE SMLS PIPE STD
FITTINGS				
3		150 x 100	1	TEE ANSI B16.9 BW STD
4		150 x 100	1	REDU ECC ANSI B16.9 BW STD
5		150 x 20	1	BONNEY THREDOLET NPT #3000
6		150	2	ELBOW LR ANSI B16.9 BW
7		100	1	ELBOW LR ANSI B16.9 BW
8		20	2	NIPPLE TBE NPT 3" LONG XS
9		20	1	CAP SCRD ANSI B16.11 #3000
FLANGES				
10		150	4	FLANGE WN ANSI B16.5 #150.RF
11		100	2	FLANGE WN ANSI B16.5 #150.RF

ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
GASKETS				
12		150	4	GASKET ANSI B16.21 #150.RF
13		100	3	GASKET ANSI B16.21 #150.RF
BOLTS				
14		19	32	95 STUD BOLT CW HVY HEX NUTS
15		16	8	89 STUD BOLT CW HVY HEX NUTS
VALVES / IN-LINE ITEMS				
16		150	2	VALVE GATE ANSI B16.10 #150.RF
17		100	1	VALVE GATE ANSI B16.10 #150.RF
18		20	1	VALVE GATE NPT #800
INSTRUMENTS				
19	FCV-2202	100	1	GLOBE VALVE
SUPPORTS				
20	12A-150-06-100/100-P E	150	1	PIPE SUPPORT TRUNNION SLIDE (ELBOW)



TEMPORARY ISO DRAWING

TEMPORARY ISO

ALL RIGHTS RESERVED THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT,DATA,OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER,EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.		
FOR		
		
TITLE PIPING ISOMETRIC DRAWING FOR		
LINE_ID:	6"-CV-B2-V-V	1 OF 2
AREA :	6"-CV-B2-V-V	
SCALE	NONE	JOB NO. AHH20E
PROJECT	DRAWING NO.	REVISION
CAP	CAP-XX-XX-DW-XXXX	
	6"-CV-B2-V-V	

REV	DATE	DGND	CHKD	APRD	APRD	DESCRIPTION

WORK NO.

TEMPORARY ISO