


FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
1		400	0.5M	PIPE
			0.2M	ANSI B36 10 PE SMLS PIPE STD
2		20		ANSI B36 10 PE SMLS PIPE XS
FITTINGS				
3		400 x 20	1	BONNEY THREDOLET NPT #3000
4		400	1	ELBOW LR ANSI B16.9 BW
FLANGES				
5		400	1	FLANGE WN ANSI B16.5 #150.RF
6	LOOSE FLG	20	1	FLANGE ANSI B16.5 #150.RF FOR EXTRUDED TUBE ENDS
ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
GASKETS				
7		400	1	GASKET ANSI B16.21 #150.RF
8		20	1	GASKET ANSI B16.21 #150.RF
BOLTS				
9		25	16	133 STUD BOLT CW HVY HEX NUTS
INSTRUMENTS				
10	PT_101_11_10_1070_1E	20	1	PRESSURE TRANSMITTER



ALL RIGHTS RESERVED THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT,DATA,OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER,EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.		
FOR		
TITLE ----- PIPING ISOMETRIC DRAWING FOR -----		
LINE_ID: A''-HE-A-1-IN 1 OF 1		
AREA : A''-HE-A-1-IN		
SCALE	NONE	JOB NO. AHH20E
PROJECT	DRAWING NO.	REVISION
CAP	CAP-XX-XX-DW-XXXX	
	A''-HE-A-1-IN	