




FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
PIPE				
1		80	4.2M	ANSI B36 10 PE SMLS PIPE STD
2		50	0.4M	ANSI B36 10 PE SMLS PIPE XS
3		20	0.2M	ANSI B36 10 PE SMLS PIPE XS
FITTINGS				
4		80 x 80	2	TEE ANSI B16.9 BW STD
5		80 x 50	1	TEE ANSI B16.9 BW STD
6		80 x 50	1	REDU ECC ANSI B16.9 BW STD
7		80 x 20	2	BONNEY THREDOLET NPT #3000
8		80	2	ELBOW LR ANSI B16.9 BW
FLANGES				
9		80	3	FLANGE WN ANSI B16.5 #150.RF
10		50	2	FLANGE WN ANSI B16.5 #150.RF
ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
FLANGES				
11		80	1	FLANGE BLIND ANSI B16.5 #150.RF
12		50	1	FLANGE BLIND ANSI B16.5 #150.RF
GASKETS				
13		80	4	GASKET ANSI B16.21 #150.RF
14		50	3	GASKET ANSI B16.21 #150.RF
BOLTS				
15		13	4	95 STUD BOLT CW HVY HEX NUTS
16		13	8	89 STUD BOLT CW HVY HEX NUTS
17		13	8	76 STUD BOLT CW HVY HEX NUTS
VALVES / IN-LINE ITEMS				
18		80	1	VALVE GATE ANSI B16.10 #150.RF
19		50	1	VALVE GATE ANSI B16.10 #150.RF
20		20	1	VALVE GATE NPT #800
21		20	1	VALVE GLOBE VOGT NPT #800
INSTRUMENTS				
22	PG_102_11_10_1070_1E	20	1	PRESSURE GAUGE
SUPPORTS				
23	12A-80-07-50/80	80	1	PIPE SUPPORT TRUNNION SLIDE (ELBOW)
24	14B-80-07-50/80	80	1	PIPE SUPPORT TRUNNION WITH ADJUSTABLE BOLT (PIPE)



TEMPORARY ISO DRAWING

ALL RIGHTS RESERVED THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT,DATA,OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER,EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.		
FOR		
		
TITLE PIPING ISOMETRIC DRAWING FOR		
LINE_ID:	8"-ET-A1-V-H-S-SUC-B	1 OF 1
AREA	8"-ET-A1-V-H-S-SUC-B	
SCALE	NONE	JOB NO. AHH20E
PROJECT	DRAWING NO.	REVISION
CAP	CAP-XX-XX-DW-XXXX	
	8"-ET-A1-V-H-S-SUC-B	
WORK NO.		