



FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
1		400	3.3M	PIPE ANSI B36 10 PE SMLS PIPE STD
2		400 x 200	1	FITTINGS REDU CONC ANSI B16.9 BW STD
3		200 x 100	1	REDU CONC ANSI B16.9 BW STD
4		400 x 25	1	BONNEY THREDOLET NPT #3000
5		400	2	ELBOW LR ANSI B16.9 BW
6		25	1	NIPPLE TBE NPT 3" LONG XS
7		25	1	NIPPLE TBE NPT 6" LONG XS
8		400	2	FLANGES FLANGE WN ANSI B16.5 #150.RF
9		100	1	FLANGE WN ANSI B16.5 #150.RF
10		25	1	FLANGE SO ANSI B16.5 #150.RF

ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
11		25	1	FLANGES FLANGE BLIND ANSI B16.5 #150.RF
12		400	2	GASKETS GASKET ANSI B16.21 #150.RF
13		100	1	GASKET ANSI B16.21 #150.RF
14		25	1	GASKET ANSI B16.21 #150.RF
15		25	32	BOLTS 133 STUD BOLT CW HVY HEX NUTS
16		13	4	64 STUD BOLT CW HVY HEX NUTS
17		400	1	VALVES / IN-LINE ITEMS VALVE GATE ANSI B16.10 #150.RF
18		25	1	VALVE GATE NPT #800
19	42D-400-10-300	400	2	SUPPORTS PIPE SUPPORT TRUNNION HORIZONTAL (PIPE)
20	28-400-05-07-H15-S	400	2	PIPE SUPPORT GUTTER TYPE FOR HORIZONTAL



TEMPORARY ISO DRAWING

ALL RIGHTS RESERVED THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT,DATA,OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER,EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.		
FOR		
		
TITLE PIPING ISOMETRIC DRAWING FOR		
LINE_ID: 16"-PRV-C1-H-OUT 1 OF 1		
AREA : 16"-PRV-C1-H-OUT		
SCALE	NONE	JOB NO. AHH20E
PROJECT	DRAWING NO.	REVISION
CAP	CAP-XX-XX-DW-XXXX	
	16"-PRV-C1-H-OUT	

REV	DATE	DGND	CHKD	APRD	APRD	DESCRIPTION