


FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
1		250	3.2M	<u>PIPE</u> ANSI B36 10 PE SMLS PIPE STD
2		250 x 100	1	<u>FITTINGS</u> REDU CONC ANSI B16.9 BW STD
3		250 x 20	2	BONNEY THREDOLET NPT #3000
4		250	3	ELBOW LR ANSI B16.9 BW
5		20	2	NIPPLE TBE NPT 3" LONG XS
6		20	2	NIPPLE TBE NPT 6" LONG XS
7		250	4	<u>FLANGES</u> FLANGE WN ANSI B16.5 #150.RF
8		100	1	FLANGE WN ANSI B16.5 #150.RF
9		20	2	FLANGE SO ANSI B16.5 #150.RF
ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
10		20	2	<u>FLANGES</u> FLANGE BLIND ANSI B16.5 #150.RF
11		250	4	<u>GASKETS</u> GASKET ANSI B16.21 #150.RF
12		100	1	GASKET ANSI B16.21 #150.RF
13		20	2	GASKET ANSI B16.21 #150.RF
14		22	48	<u>BOLTS</u> 114 STUD BOLT CW HVY HEX NUTS
15		13	8	57 STUD BOLT CW HVY HEX NUTS
16		250	2	<u>VALVES / IN-LINE ITEMS</u> VALVE GATE ANSI B16.10 #150.RF
17		20	2	VALVE GATE NPT #800
18	EV-3302	100	1	<u>INSTRUMENTS</u> ANGLE VALVE
19	32-250-08-H15	250	1	<u>SUPPORTS</u> PIPE SUPPORT BEAM TYPE (SHAPE)
20	11B-250-08-150-S	250	1	PIPE SUPPORT TRUNNION FIX (PIPE)
21	11A-250-08-150-S	250	1	PIPE SUPPORT TRUNNION FIX (ELBOW)
22	32-250-10-A10	250	1	PIPE SUPPORT BEAM TYPE (SHAPE)



TEMPORARY ISO DRAWING

ALL RIGHTS RESERVED THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT, DATA, OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.		
FOR		
TITLE PIPING ISOMETRIC DRAWING FOR		
LINE_ID: 10"-PRV-C2-H-D-IN 1 OF 1		
AREA : 10"-PRV-C2-H-D-IN		
SCALE	NONE	JOB NO. AHH20E
PROJECT	DRAWING NO.	REVISION
CAP	CAP-XX-XX-DW-XXXX	
	10"-PRV-C2-H-D-IN	