


FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
1 2 3		350	5.9M	PIPE ANSI B36 10 PE SMLS PIPE STD ANSI B36 10 PE SMLS PIPE STD ANSI B36 10 PE SMLS PIPE XS
		250	0.2M	
		20	0.4M	
FITTINGS				
4		350 x 250	1	REDU CONC ANSI B16.9 BW STD
5		350 x 20	4	BONNEY THREDOLET NPT #3000
6		350	5	ELBOW LR ANSI B16.9 BW
FLANGES				
7		350	6	FLANGE WN ANSI B16.5 #150.RF
8		250	1	FLANGE WN ANSI B16.5 #150.RF

ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
GASKETS				
9		350	7	GASKET ANSI B16.21 #150.RF
10		250	1	GASKET ANSI B16.21 #150.RF
BOLTS				
11		25	12	306 STUD BOLT CW HVY HEX NUTS
12		25	12	133 STUD BOLT CW HVY HEX NUTS
13		25	36	127 STUD BOLT CW HVY HEX NUTS
14		22	12	114 STUD BOLT CW HVY HEX NUTS
VALVES / IN-LINE ITEMS				
15		350	1	VALVE WFR CHK MISSION K #150.RF
16		350	2	VALVE GATE ANSI B16.10 #150.RF
17		20	4	VALVE GATE NPT #800
INSTRUMENTS				
18	PG_102_11_10_1070_1E	20	1	PRESSURE GAUGE
SUPPORTS				
19	14A-350-08-250/250	350	1	PIPE SUPPORT TRUNNION WITH ADJUSTABLE BOLT (ELBOW)
20	11A-350-08-250	350	1	PIPE SUPPORT TRUNNION FIX (ELBOW)

CONT. ON
14"-TT-B1-S-G-N-DIS-A
E 147306
N 97979
EL +2878



ALL RIGHTS RESERVED THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT, DATA OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.		
FOR		
TITLE PIPING ISOMETRIC DRAWING FOR		
LINE_ID:	14"-TT-B1-S-G-N-DIS-B	1 OF 1
AREA :	14"-TT-B1-S-G-N-DIS-B	
SCALE	NONE	JOB NO. AHH20E
PROJECT	DRAWING NO.	REVISION
CAP	CAP-XX-XX-DW-XXXX	
	14"-TT-B1-S-G-N-DIS-B	

REV	DATE	DGND	CHKD	APRD	APRD	DESCRIPTION

WORK NO.

TEMPORARY ISO

EXTRACT DATE : 24 JUL 2019 13:34 ()