


FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
1		350	6.9M	PIPE
				ANSI B36 10 PE SMLS PIPE STD
2		20	0.2M	ANSI B36 10 PE SMLS PIPE XS
FITTINGS				
3		350 x 350	1	TEE ANSI B16.9 BW STD
4		350 x 20	2	BONNEY THREDOLET NPT #3000
5		350	4	ELBOW LR ANSI B16.9 BW
FLANGES				
6		350	6	FLANGE WN ANSI B16.5 #150.RF
ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
GASKETS				
7		350	6	GASKET ANSI B16.21 #150.RF
BOLTS				
8		25	12	306 STUD BOLT CW HVY HEX NUTS
9		25	12	133 STUD BOLT CW HVY HEX NUTS
10		25	24	127 STUD BOLT CW HVY HEX NUTS
VALVES / IN-LINE ITEMS				
11		350	1	VALVE WFR CHK MISSION K #150.RF
12		350	1	VALVE GATE ANSI B16.10 #150.RF
13		20	2	VALVE GATE NPT #800
SUPPORTS				
14	11A-350-06-250	350	1	PIPE SUPPORT TRUNNION FIX (ELBOW)



ALL RIGHTS RESERVED
THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT,DATA,OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER,EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.

FOR



TITLE PIPING ISOMETRIC DRAWING FOR
LINE_ID: 14"-TT-A2-S-S-O-DIS-A 2 OF 2
AREA : 14"-TT-A2-S-S-O-DIS-A

SCALE NONE	JOB NO. AHH20E	REVISION
PROJECT CAP	DRAWING NO. CAP-XX-XX-DW-XXXX	14"-TT-A2-S-S-O-DIS-A

WORK NO.

EXTRACT DATE : 24 JUL 2019 13:35 ()