


FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
1		350	3.8M	PIPE
				ANSI B36 10 PE SMLS PIPE STD
2		20	0.2M	ANSI B36 10 PE SMLS PIPE XS
FITTINGS				
3		350 x 350	1	TEE ANSI B16.9 BW STD
4		350 x 20	2	BONNEY THREDOLET NPT #3000
5		350	2	ELBOW LR ANSI B16.9 BW
FLANGES				
6		350	2	FLANGE WN ANSI B16.5 #150.RF


ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
GASKETS				
7		350	3	GASKET ANSI B16.21 #150.RF
BOLTS				
8		25	12	133 STUD BOLT CW HVY HEX NUTS
9		25	12	127 STUD BOLT CW HVY HEX NUTS
VALVES / IN-LINE ITEMS				
10		350	1	VALVE GATE ANSI B16.10 #150.RF
11		20	2	VALVE GATE NPT #800
SUPPORTS				
12	11A-350-06-250	350	1	PIPE SUPPORT TRUNNION FIX (ELBOW)



TEMPORARY ISO DRAWING

ALL RIGHTS RESERVED
THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT, DATA OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.

FOR

**CHIYODA CORPORATION**

TITLE

PIPING ISOMETRIC DRAWING FOR

LINE_ID:

14"-TT-A1-S-G-N-SUC-A

1 OF 2

AREA

: 14"-TT-A1-S-G-N-SUC-A

SCALE

NONE

JOB NO.

AHH20E

PROJECT


DRAWING NO.

REVISION

CAP

CAP-XX-XX-DW-XXXX

14"-TT-A1-S-G-N-SUC-A



REV	DATE	DGND	CHKD	APRD	APRD	DESCRIPTION

WORK NO.