


FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
				<u>PIPE</u>
1		450	4.0M	ANSI B36 10 PE SMLS PIPE STD
2		40	0.2M	ANSI B36 10 PE SMLS PIPE XS
				<u>FITTINGS</u>
3		600 x 450	1	REDU ECC ANSI B16.9 BW STD
4		450 x 300	1	REDU ECC ANSI B16.9 BW STD
5		450 x 40	1	BONNEY THREDOLET NPT #3000
6		450	4	ELBOW LR ANSI B16.9 BW
				<u>FLANGES</u>
7		450	4	FLANGE WN ANSI B16.5 #150.RF
8		300	1	FLANGE WN ANSI B16.5 #150.RF
9		40	1	FLANGE SCRDR BOSS ANSI B16.5 #150.RF


ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
FLANGES				
10		40	1	FLANGE BLIND ANSI B16.5 #150.RF
GASKETS				
11		450	3	GASKET ANSI B16.21 #150.RF
12		300	1	GASKET ANSI B16.21 #150.RF
13		40	1	GASKET ANSI B16.21 #150.RF
BOLTS				
14		29	48	146 STUD BOLT CW HVY HEX NUTS
15		22	12	114 STUD BOLT CW HVY HEX NUTS
16		13	4	70 STUD BOLT CW HVY HEX NUTS
VALVES / IN-LINE ITEMS				
17		450	1	VALVE GATE ANSI B16.10 #150.RF
SUPPORTS				
18	12A-450-14-300/300-S	450	1	PIPE SUPPORT TRUNNION SLIDE (ELBOW)



TEMPORARY ISO DRAWING

ALL RIGHTS RESERVED
THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT,DATA,OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER,EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.

FOR

**CHIYODA CORPORATION**

TITLE

PIPING ISOMETRIC DRAWING FOR

LINE_ID:

18"-PHE-A2-Y-N-OUT

1 OF 1

AREA

: 18"-PHE-A2-Y-N-OUT

SCALE

NONE

JOB NO.

AHH20E

PROJECT

DRAWING NO.

REVISION

CAP

CAP-XX-XX-DW-XXXX

18"-PHE-A2-Y-N-OUT

WORK NO.

REV	DATE	DGND	CHKD	APRD	APRD	DESCRIPTION