


FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
1		600	0.8M	PIPE
		250	5.9M	ANSI B36 10 PE SMLS PIPE STD
2				ANSI B36 10 PE SMLS PIPE STD
FITTINGS				
3		600 x 250	2	TEE ANSI B16.9 BW STD
4		600	1	CAP LONG ANSI B16.9 BW STD
5		250	8	ELBOW LR ANSI B16.9 BW
FLANGES				
6		250	2	FLANGE WN ANSI B16.5 #150.RF
ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
GASKETS				
7		250	6	GASKET ANSI B16.21 #150.RF
BOLTS				
8		22	24	121 STUD BOLT CW HVY HEX NUTS
9		22	24	114 STUD BOLT CW HVY HEX NUTS
VALVES / IN-LINE ITEMS				
10		250	2	VALVE GATE ANSI B16.10 #150.RF




TEMPORARY ISO DRAWING

REV	DATE	DGND	CHKD	APRD	APRD	DESCRIPTION

ALL RIGHTS RESERVED
THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT, DATA, OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.

FOR

**CHIYODA CORPORATION**

TITLE
PIPING ISOMETRIC DRAWING FOR

LINE_ID: 10"-CV-B1-UODD-OUT 1 OF 2

AREA : 10"-CV-B1-UODD-OUT

SCALE NONE JOB NO. AHH20E

PROJECT DRAWING NO. CAP-XX-XX-DW-XXXX

REVISION

10"-CV-B1-UODD-OUT

WORK NO.