


FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
1 2 3		350	2.5M	PIPE ANSI B36 10 PE SMLS PIPE STD
		250	0.2M	ANSI B36 10 PE SMLS PIPE STD
		20	0.2M	ANSI B36 10 PE SMLS PIPE XS
4 5 6		350 x 250	1	FITTINGS REDU CONC ANSI B16.9 BW STD
		350 x 20	2	BONNEY THREDOLET NPT #3000
		350	3	ELBOW LR ANSI B16.9 BW
7 8		350	3	FLANGES FLANGE WN ANSI B16.5 #150.RF
		250	1	FLANGE WN ANSI B16.5 #150.RF
		ERECTION MATERIALS		
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
9 10		350	4	GASKETS GASKET ANSI B16.21 #150.RF
		250	1	GASKET ANSI B16.21 #150.RF
				BOLTS
11 12 13		25	12	306 STUD BOLT CW HVY HEX NUTS
		25	12	133 STUD BOLT CW HVY HEX NUTS
		22	12	114 STUD BOLT CW HVY HEX NUTS
14 15 16		350	1	VALVES / IN-LINE ITEMS VALVE WFR CHK MISSION K #150.RF
		350	1	VALVE GATE ANSI B16.10 #150.RF
		20	2	VALVE GATE NPT #800
17  18	PG_102_11_10_1070_1E  14A-350-08-250/250	20	1	INSTRUMENTS PRESSURE GAUGE
				SUPPORTS
		350	1	PIPE SUPPORT TRUNNION WITH ADJUSTABLE BOLT (ELBOW)



TEMPORARY ISO DRAWING

ALL RIGHTS RESERVED  
THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT, DATA, OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER, EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.

FOR		
TITLE PIPING ISOMETRIC DRAWING FOR		
LINE_ID:	14"-TT-C1-S-G-N-DIS-A	1 OF 2
AREA :	14"-TT-C1-S-G-N-DIS-A	
SCALE	NONE	JOB NO. AHH20E
PROJECT	DRAWING NO.	REVISION
CAP	CAP-XX-XX-DW-XXXX	
	14"-TT-C1-S-G-N-DIS-A	

WORK NO.

EXTRACT DATE : 24 JUL 2019 13:34 ( )