


FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
				<u>PIPE</u>
1		150	1.2M	ANSI B36 10 PE SMLS PIPE STD
2		100	2.2M	ANSI B36 10 PE SMLS PIPE STD
				<u>FITTINGS</u>
3		150 x 100	1	REDU ECC ANSI B16.9 BW STD
4		150 x 100	1	TEE ANSI B16.9 BW STD
5		150 x 20	1	BONNEY THREDOLET NPT #3000
6		150	2	ELBOW LR ANSI B16.9 BW
7		100	1	ELBOW LR ANSI B16.9 BW
8		20	2	NIPPLE TBE NPT 3" LONG XS
9		20	1	CAP SCRD ANSI B16.11 #3000
				<u>FLANGES</u>
10		150	2	FLANGE WN ANSI B16.5 #150.RF
11		100	2	FLANGE WN ANSI B16.5 #150.RF

ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
12 13		150	2	GASKETS GASKET ANSI B16.21 #150.RF
		100	3	GASKET ANSI B16.21 #150.RF
14 15		19	16	BOLTS 95 STUD BOLT CW HVY HEX NUTS
		16	8	89 STUD BOLT CW HVY HEX NUTS
16 17		150	1	VALVES / IN-LINE ITEMS VALVE GATE ANSI B16.10 #150.RF
		20	1	VALVE GATE NPT #800
18	FCV-2202	100	1	INSTRUMENTS GLOBE VALVE
SUPPORTS				
19	11B-150-06-100-S	150	1	PIPE SUPPORT TRUNNION FIX (PIPE)



TEMPORARY ISO DRAWING

REV	DATE	DGND	CHKD	APRD	APRD	DESCRIPTION

ALL RIGHTS RESERVED THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT, DATA OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.		
FOR		
TITLE PIPING ISOMETRIC DRAWING FOR		
LINE_ID: 6"-CV-A2-H-H-H-D 2 OF 2		
AREA : 6"-CV-A2-H-H-H-D		
SCALE	NONE	JOB NO. AHH20E
PROJECT	DRAWING NO.	REVISION
CAP	CAP-XX-XX-DW-XXXX	
	6"-CV-A2-H-H-H-D	

WORK NO.

EXTRACT DATE : 11 SEP 2019 09:36 ()