



FABRICATION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
1		600	0.6M	PIPE
		250	5.1M	ANSI B36 10 PE SMLS PIPE STD
2				ANSI B36 10 PE SMLS PIPE STD
FITTINGS				
3		600 x 250	1	TEE ANSI B16.9 BW STD
4		250 x 25	1	BONNEY THREDOLET NPT #3000
5		600	1	CAP LONG ANSI B16.9 BW STD
6		250	4	ELBOW LR ANSI B16.9 BW
7		25	2	NIPPLE TBE NPT 3" LONG XS
8		25	1	CAP SCRD ANSI B16.11 #3000
FLANGES				
9		250	1	FLANGE WN ANSI B16.5 #150.RF
ERECTION MATERIALS				
NO	REMARKS	SIZE (MM)	QTY	DESCRIPTION
GASKETS				
10		250	2	GASKET ANSI B16.21 #150.RF
BOLTS				
11		22	12	121 STUD BOLT CW HVY HEX NUTS
VALVES / IN-LINE ITEMS				
12		25	1	VALVE GATE NPT #800



TEMPORARY ISO DRAWING

ALL RIGHTS RESERVED
THIS DOCUMENT AND ANY DATA AND INFORMATION CONTAINED THEREIN ARE CONFIDENTIAL AND THE PROPERTY OF CHIYODA CORPORATION(CHIYODA) AND THE COPYRIGHT THEREIN IS VESTED IN CHIYODA. NO PART OF THIS DOCUMENT,DATA,OR INFORMATION SHALL BE DISCLOSED TO OTHERS OR REPRODUCED IN ANY MANNER OR USED FOR ANY PURPOSE WHATSOEVER,EXCEPT WITH THE PRIOR WRITTEN PERMISSION OF CHIYODA.

FOR

**CHIYODA CORPORATION**

TITLE
PIPING ISOMETRIC DRAWING FOR

LINE_ID: 10"-CN-B2-UODD-IN 4 OF 4

AREA : 10"-CN-B2-UODD-IN

SCALE NONE JOB NO. AHH20E

PROJECT DRAWING NO. CAP-XX-XX-DW-XXXX

REVISION

10"-CN-B2-UODD-IN

REV	DATE	DGND	CHKD	APRD	APRD	DESCRIPTION

WORK NO.